

NOLENSVILLE AT PETTUS PRV
MWS PROJECT NUMBER: 23WG0064
COUNCIL DISTRICT 31 & 04



6804 NOLENSVILLE PIKE
18100005100

6820 NOLENSVILLE PIKE
18100005101

PROPOSED 8" PRV VAULT
(1) 8" PRV
(1) 8" FLOW METER
(2) 8" RESILIENT SEAT GATE VALVES
APPROX. 98 L.F. OF 8" RJ-DIP PC 350

INSTALL 6"X6" TAPPING SLEEVE
AND 6" RESILIENT SEAT GATE VALVE
INSTALL 8"X6" REDUCER

6815 NOLENSVILLE PIKE
18100001000

7115 SOUTHPOINT PKWY
18100008400




NOLENSVILLE PIKE

INSTALL 12"X8" TAPPING SLEEVE
AND 8" RESILIENT SEAT GATE VALVE

6821 NOLENSVILLE PIKE
18100019600

FH 82044

7111 SOUTHPOINT PKWY
18100030100

-  Water System Valve
-  Water Pressure Boundary Valves
-  Water Main (In Service)

NOTE: THIS SKETCH IS GENERAL IN NATURE
AND WAS NOT SURVEYED - MODIFICATIONS
TO BE PERFORMED BY MWS FORCES AND
ADJUSTED TO ACTUAL CONDITIONS.

